



NOTES:

1. ALL WOOD MATERIAL MUST BE NEW PRESSURE TREATED
PAINTED SURFACES ARE NOT ACCEPTABLE
2. THE CONTRACTOR SHALL GROUND THE SERVICE FACILITIES. THE CONTRACTOR SHALL DRIVE THE GROUND ROD(S) ON METER SIDE OF PEDESTAL TO AVOID COMPANY CABLES
3. THIS INSTALLATION IS AN ALTERNATE FOR MOBILE HOME PARKS AND MOBILE HOMES THAT ARE NOT APPROVED FOR THE INSTALLATION OF A METER ON THE SIDE
4. NEUTRAL MUST BE MARKED
5. GROUNDING IN ACCORDANCE WITH NEC

200A / 320A METER FITTING
FREE STANDING – UNDERGROUND INSTALLATION
120/240 VOLT, 1 PHASE, 3 WIRE
120/240 VOLT, 3 PHASE, 4 WIRE
225A MAXIMUM SERVICE



AUBURN ELECTRIC DEPT.

Freestanding-Underground-Riser

NOT TO SCALE

DATE: 21-NOV-2024