



Items owned and installed by customer

- 1 4" x 4" x 16' or 2" x 10" x 16' minimum, continuous single structure. No timber
- 2 Meter socket and distribution panel (up to 200 A, 120/240 V)
- 3 Ground wire, in accordance with NEC
- 4 Ground rods, in accordance with NEC  
Tethered with Ground Wire
- 5 2" x 4" brace (two required)
- 6 Service entrance conductors - 18" out of weatherhead minimum
- 7 Insulated clevis (point of attachment)
- 8 Disconnect Switch and GFCI Outlet(s)

Items owned and installed by AE

- 9 Service line
- 10 Meter

City of



**AUBURN ELECTRIC DEPT.**

Temporary OH Service Installation

NOT TO SCALE

DATE: 02-JUN-2025