



Items Owned and Installed by Customer

1. Customer-owned meter pole
2. Meter base/socket
3. Ground wire, in accordance with NEC
4. Ground rods, in accordance with NEC  
Tethered with Ground Wire
5. 2" Pipe Cut off 6" Above Ground
6. Disconnect and GFCI Outlet(s)

Items Owned and Installed by AE

7. Meter



## AUBURN ELECTRIC DEPT.

Temporary URD 200A Service

NOT TO SCALE

DATE: 02-JUN-2025